

AVERAGE UNIT BID PRICES (Awarded Contractors)

April 2007 - March 2008

Major Items

P. S. & E. Bureau/Bid Analysis Construction Section
New Mexico Department of Transportation

Item Number	Spec Year	Item Description	Unit of Meas.	Total Quantity	Average Unit Price
201000	07	CLEARING AND GRUBBING	LS	28	\$ 42,736.11
203000	07	UNCLASSIFIED EXCAVATION	C.Y.	1,672,771.00	\$ 5.29
203100	07	BORROW	C.Y.	1,483,803.00	\$ 5.65
207000	07	SUBGRADE PREPARATION	S.Y.	2,800,681.00	\$ 1.09
303000	07	BASE COURSE	TON	1,039,039.00	\$ 10.98
304000	07	BASE COURSE	TON	289,747.00	\$ 16.24
304800	07	BASECOURSE TESTING BY THE CONTRACTOR	LS	16	\$ 16,236.56
402320	07	64-22 PERFORM. GRADE ASPHALT MAT'L	TON	12,130.00	\$ 251.26
402325	07	64-28 PERFORM. GRADE ASPHALT MAT'L	TON	675.00	\$ 500.00
402350	07	70-22 PERFORM. GRADE ASPHALT MAT'L	TON	15,662.00	\$ 365.13
402355	07	70-28 PERFORM. GRADE ASPHALT MAT'L	TON	1,664.00	\$ 422.01
402375	07	76-22 PERFORM. GRADE ASPHALT MAT'L	TON	2,665.00	\$ 400.80
402460	07	HYD. LIME	TON	27,699.00	\$ 111.06
403700	07	OPEN GRADED FRICTION COURSE	TON	26,507.00	\$ 55.08
404000	07	OPEN GRADED FRICTION COURSE	TON	42,658.00	\$ 72.00
423220	07	HMA SP-II	TON	295,100.00	\$ 43.52
423240	07	HMA SP-III	TON	181,935.00	\$ 35.17
423260	07	HMA SP-IV	TON	62,900.00	\$ 38.00
511000	07	STRUCTURAL CONCRETE, CL A	C.Y.	10,182.84	\$ 430.58
511300	07	SUBSTRUCTURE CONCRETE CLASS A	C.Y.	1,128.10	\$ 425.49
512000	07	SUPERSTRUCTURE CONCRETE	C.Y.	6,884.30	\$ 500.11
518045	07	PRESTRESS.CONC.BRIDGE MEMBER TYPE 45	L.F.	794	\$ 267.00
518054	07	PRESTRESS.CONC.BRIDGE MEMBER TYPE 54	L.F.	2,518.25	\$ 262.11
518055	07	PRESTRESS.CONC.BRIDGE MEMBER TYPE BT-54	L.F.	2,520.00	\$ 270.00
540060	07	REINFORCING BARS GRADE 60	LB	1,394,241.00	\$ 1.03
540160	07	EPOXY COATED REIN BARS GR 60	LB	1,365,784.00	\$ 1.17
601000	07	REMOVL OF STRUCT AND OBSTRUCT	LS	52	\$ 70,895.96
601110	07	REMOVAL OF SURFACING	S.Y.	764,200.00	\$ 3.70
613000	07	CLNG CULVTS & DRNAGE STRUCT	LS	6	\$ 19,416.67
618000	07	TRAFFIC CONTROL MANAGEMENT	LS	54	\$ 106,418.68
621000	07	MOBILIZATION	LS	55	\$ 434,054.38
632202	07	EROSION CONTROL COMPOST	ACRE	128.75	\$ 4,991.07
702800	07	TRAFFIC CONTROL PLAN	LS	1	\$ 19,000.00
801000	07	CONSTRUCTION STAKING BY CONTR	LS	47	\$ 78,210.83
901000	07	CONTRACTOR PROCESS QUALITY CONTROL	LS	18	\$ 141,548.56